


Panattoni Park Koszalin offers 58,419 sq m of industrial space suitable for light production, logistic and e-commerce activities, and it is a proposal for companies looking to develop in Pomerania, especially because it offers the benefits of being located in the Słupsk Special Economic Zone.

← **SZCZECIN**
170 km, 100 min

→ **KOSZALIN CITY CENTER**
3 km, 6 min
GDAŃSK
190 km, 3 hrs



LOCATION IS KEY

DEVELOPMENT SPACE

Panattoni Park Koszalin offers 58,419 sq m of industrial space suitable for light production, logistic and e-commerce activities.

ACCESS


The park is ideally located - a 5-minute drive from the S6 motorway and 3 km from the city center. The proximity of the Baltic Sea guarantees connections with Scandinavia, and important roads to Berlin and Kaliningrad lead nearby.

PUBLIC TRANSPORT

Existing bus stop 850 m from the Park is providing connection with 2 bus lines.

LABOR FORCE

Available resources of qualified personnel with a population of over 100,000.



The park is located near the S6 expressway, which connects the S11 to Szczecin and further to Germany.

BUILDING INFORMATION


Building 1	41,558 sq m
Building 2	13,558 sq m
Building 3	3,303 sq m

WAREHOUSE

Column grid 12 m × 22,5 m
 Clear height 10 m
 ESFR sprinkler system
 Light intensity in the hall 150–400 lux
 Skylights min 2 %
 Floor loading 5 t/sq m

OFFICE PREMISES

Clear height 3 m
 Light intensity 500–700 lux
 Built to suit solution



STANDARD TECHNICAL SPECIFICATION

- 1 SUPPORTING STRUCTURE**
 Pad or pilot foundations, insulated plinth panels up to 30 cm above floor.
- 2 FLOOR**
 Fibre reinforced concrete floor, PE membrane, cut joints, 18 cm thick, surface treated with hardener.
- 3 ROOF**
 Corrugated steel sheets, mineral wool insulation, PVC membrane.
- 4 FAÇADE**
 Horizontal sandwich panels with mineral wool insulation.
- 5 DOCKS**
 1x electrically operated 3 x 3.2 m dock for each 1,000 sq m of hall.
- 6 HALL INSTALLATIONS**
 Gas Sahara heaters or infrared gas radiators, heating according to norms for warehousing.
- 7 PRODUCTION UPGRADE (OPTIONAL)**
 Increased façade and roof insulation.
- 8 OFFICES**
 2 level custom designed in-built, incl. offices, socials, locker rooms, day room, excl. furniture and appliance.
- 9 OUTSIDE AREAS**
 Hard areas from concrete pavers, sloped for drainage.

